

StormTrap®

MODULAR CONCRETE STORMWATER MANAGEMENT

SiteSaver® Treatment Solutions

Emerging Technologies – FSA Conference 2022

Sean Agans - General Sales Manager - Southeast



Stormwater Management Solutions





Detention

Retention



Stormwater Management Solutions



Stormwater LID

Rainwater Harvesting Infiltration Biofiltration Pervious Surfaces



Treatment

Filtration Oil & Water Separation Sedimentation Trash & Debris Removal Treatment Train Pre-treatment Storage Filtration




SiteSaver[®]


SiteSaver is a unique hydrodynamic separator that utilizes trash containment devices, inclined plate technology and baffles to capture and easily remove trash and debris, floatables, hydrocarbons and sediment from waterways




Verified








Components Net/ Basket Configurations









Flow Events









High Flow



Nets/Baskets vs. Vertical Screens

Nets/Baskets












Innovative Components Inclined Plates

- Small footprint (stacked cells)
- Lower installation cost
- Self-cleaning cells
- Easy placement/design








Minimal Head Loss





 Standard design for head loss shall not exceed 4" throughout the entire water quality device



SiteSaver Approvals



Verified



Certified HDS















SiteSaver Treatment Efficiencies

SiteSaver STSS Flow Rates and Removal Efficiencies

STSS – Model	NJDEP Testing	NJCAT Coarse Particle Test	OK-110	SPS 125µm	SPS 175µm
STSS - 4	4.32 CFS	4.32 CFS	2.96 CFS	4.96 CFS	9.72 CFS
STSS - 7	7.56 CFS		5.18 CFS	8.68 CFS	17.01 CFS
STSS - 12	12.96 CFS		8.87 CFS	14.88 CFS	29.17 CFS
STSS - 18	19.44 CFS		13.31 CFS	22.32 CFS	43.75 CFS

D-50	48	172	110	125	175
Removal %	50%	98%	80%	80%	80%





Certified HDS



Verified

Installation








Maintenance



SiteSaver Net Replacement / Basket Cleaning









Site Specific Data

Peak Flow Rate = 32.5 CFS

Water Quality Flow = 4.06 CFS

Design sediment requirement: 50% TSS (NJDEP)

Model = STSS-4

Case Study

Second Street Youth Center – Plainfield, NJ





Second Street Youth Center









Site Specific Data

Peak Flow Rate: 32.5 CFS

Water Quality Flow: 2.95 CFS | 8.86 CFS

Design Sediment Requirement: 80% TSS

Model = 1 STSS-4 and 2 STSS 12

Case Study


LATC Modernization





LATC Modernization









Site Specific Data

Peak Flow Rate = 12 CFS | 22 CFS Water Quality Flow = 2.5 CFS | 4.9 CFS

Design Sediment Requirement: 80% TSS

Model = STSS-4 and STSS-7

Case Study

Cottonwood Drive Widening Project





Cottonwood Drive Widening Project







StormTrap Complete Services



- Flow calculations
- Budget estimate for the system & installation
- Complete set of drawing
- Written CSI specification
- 24 48 hour turnaround



- Pre-construction meeting
- Predetermined shipping sequence / schedule
- Project Manager on site during installation
- 6 8 week lead time




Maintenance Services

- Maintenance services available for all products utilizing netting technology
- Replacement nets
- System Monitoring



StormTrap.com - Stay informed about our solutions


Request a Lunch & Learn



View Project Profiles & Videos













Questions?

Thank you

Sean Agans - General Sales Manager - Southeast

sagans@stormtap.com

646-242-9956

